## HIGH ROCK

## **Standard Features**

## **Exterior** –

- Wind Zone I (STD), II (OPT) and III (OPT)
- 2x4 Walls 16" On Center with R-13 Insulation
- 7/16" O.S.B. Sheathing Wrap and Roof
- 3/12 (Nominal) Roof, Trusses 24" On Center
- 4/12 Pitch Roof On Single Sections 16 Wides
- Fully Vented Soffit and Hardi Plank Fascia
- 30 Year GAF Architectural Shingles
- Continuous Ridge Vent

- Exterior Hose Bibb Front and Back
- Kwikset® Door Hardware
- Low E Insulated with Argon Gas Filled Windows with Screens
- Insulated 6-Panel Steel Front Door with Storm Door
- Insulated 9-Light Rear Door with Storm Door
- Exterior GFI Receptacles Front and Back
- · Exterior Light at Each Door

## **Interior**

- Double 2x3 Marriage Walls 16" on Center
- 2x4 Top and Bottom Plates On 2x4 Walls
- Residential 1/2" Finished Drywall Throughout
- 19/32" O.S.B. T&G Floor Decking; Glued and Nailed
- R22 Floor Insulation
- 25oz Shaw Carpeting with 5.3 lb. Rebond Pad
- Single Sections have Lino Throughout
- Congoleum® Linoleum in all Wet Areas
- 6-Square Panel Interior Doors
- · Crown and Baseboard White
- DuraCraft® 42" Overhead Cabinets in Kitchen
- Laminated Countertops with Backsplash
- Stainless Steel Double Bowl Sink in Kitchen
- Stainless Steel Appliances Includes:
  - 18 Cubic Foot Top-Mount Refrigerator with Ice Maker
  - 30" 5 Burner Electric Range Smooth top
  - Dishwasher
- 60" Fiberglass Shower (Most Multi-Sections and

several Single Sections)

- Square Sinks in Bathrooms
- 200 AMP Main Service Panel
- LED Recessed Light Package Throughout
- Whole House Ventilation System
- ecobee® Smart Thermostat
- Smoke Detectors
- GFI Receptacles Where Required by Code
- Dryer Receptacle and Vent
- Pfister\* Faucets Throughout
- 40 Gallon Hybrid Water Heater with Overflow Pan
- PEX Supply Lines
- Main Water Shut Off in Utility and Shut Offs at all Fixtures
- Washer and Dryer Hook Ups
- Wire and Brace in Primary Bedroom, Living Room and Family Room
- 2" Mini Blinds on all Windows
- 8' Flat Smooth Ceiling



